



Normand House Coed Eva

Client: Bron Afon • Materials: GEPS, Silicone Render
Sector: Residential, High Rise • Build Type: Refurbishment



Normand House is a refurbishment project and is part of a £500 million scheme set by Bron Avon Housing Association, to upgrade social housing accommodation to align with the requirements of the Welsh Housing Quality Standard.

turn reduce their fuel/ energy bills. A silicone top coat was then applied to give a smooth rendered finish providing the customer with a more aesthetically pleasing dwelling.

The Objective

The Challenge



The original objective for the first part of this scheme, was the refurbishment of two blocks of social housing in Coed Eva, Cwmbran. Due to poor condition of neighbouring blocks, it was agreed to increase the original works to include the adjoining sites.

With every large refurbishment project comes a number of challenges and while external wall insulation is a significant undertaking, it presented minimum disruption to tenants which was key during the duration of the work.



P&P Building and Roofing Contractor were appointed by Bron Afon to carry out the refurbishment works, to renovate the four blocks utilizing SPSenviowall's high-quality external wall insulation systems and render materials.

Before applying external wall insulation, all cavity insulation that had previously been installed was removed and high impact reinforcement mesh was used to further protect communal areas. All blocks are of three story cavity brick and block construction.

Carried out over the duration of eight months, P&P and SPSenviowall successfully installed 3,500m² of 90mm grey EPS insulation, which provided the residents with a more comfortable living environment by improving the thermal performance and in

The building steps back at the parapet areas with timber frame and internal light weight block. All framework voids were insulated with quilt to reduce the dew point and areas requiring extra fire breaks were identified. Originally the only choice of colour was

CPD events available

For those interested in finding out more, we provide informative RIBA accredited CPD sessions.



To book a CPD sessions, please call: 01782 367600



0800 612 4662



sales@benx.co.uk



benx.co.uk

cream, however it was decided that some colour creativity was necessary to break-up the large neutral “wall of cream” by finishing inset areas with a light grey for a more pleasing aesthetic.

The Benefits

The newly refurbished buildings are a huge improvement to the original brick buildings, leaving tenants delighted with reports of the huge difference in their living conditions due to the insulation making their homes warmer and more comfortable to live in whilst saving on fuel bills.

Prior to the works carried out the u-value calculation was 1.2w(m²k) and was much improved when the insulation works achieved 0.28w(m²k) when completed in August 2016.

Bron Afon are also delighted in the works carried out. Delivery of the project was on time with minimal disruption to the tenants and are delighted with how P&P worked closely with SPSenviowall to ensure the requirements and needs of this project were met.

CPD events available

For those interested in finding out more, we provide informative RIBA accredited CPD sessions.



To book a
CPD sessions,
please call:
01782 367600



0800 612 4662



sales@benx.co.uk



benx.co.uk